REVISION TO CHAPTER 8 AN OVERVIEW OF THE MAIN CHANGES BEING INTRODUCED





OUTLINE

- Project Need
- Standard Systems of Control
- Temporary TrafficManagement Design
- Traffic Management Operations
- Vulnerable Road Users



GAP ANALYSIS

- Traffic Management Classification
 not consistent with design standards
 - O DMRB
 - O DMURS
- **?** Variance in interpretation on Types
 - Type A
 - Type B
 - o Type C
- Urban Areas
- Semi-Static Works
- Motorway Network




SCOPE AND GOAL

- **?** Clear guidance
- Ensure consistency
- Standards appropriate to the risk



STANDARD SYSTEMS OF CONTROL

RISK ASSESSME



Severity		Risk	
Major	Medium	High	High
Serious	Low	Medium	High
Minor	Low	Low	Medium
	Unlikely	Likely	Very Likely
		Likelihood	



8. Temporary Traffic Measures and Signs for Roadworks

CHAPTER 8

STANDARD VS DESIGNER

Duration of Works Traffic Volume Visibility



Hazards




STANDARD OPERATING PROCEDURE

Urban and Low Speed (Level 1 Roads)

Temporary Traffic Signals Operation

Introduction

A Temporary Traffic Signals system is suitable for Level 1 roads with a speed limit up to 60km/h. The TTOS should ensure that the Cardaí have been notified in advance of the operation. TTM operatives either manually operate, pre-programme or set line traffic signals to vehicle actuated mode. Tapers are at 45° with cones at 1m centres. Traffic volumes are monitored throughout the works.



Roadworks Type	No. Signs / Cumulative Distance (m)	Sign Visibility (m)	Longitudinal Safety Zone (m)	Lateral Safety Zone (m)	Max Cone / Lamp Spacing (m)
Level 1 (I) A	2/20	25	0.5	0.5	3 / N/A
Level 1 (i) B	1 / 10	25	0.5	0.5	3 / N/A
Level 1 (ii) A	2/30	35	0.5	0.5	3/6
Level 1 (ii) B	2/30	35	0.5	0.5	3/6
Level 1 (III) A	2 / 40	50	5	0.5	376
Level 1 (iii) B	2/40	50	5	0.5	376
Level 1 (iv) A	3 / 60	60	15	0.5	6/12
Lovel 1 (iv) B	2 / 40	60	15	0.5	6/12

Signal Sequence

- Red time is set by Operative
- Green time is set by Operative
- Amber 3 seconds
- Red time is set by Operative

Signal Checks

- Balleries
- Bulb/LEDs operating
- Signals communicating with each other
- Housing is in good condition

Summary Criteria

Max Speed Limit (km/h)	Coned Area Length (m)	Max Traffic Flow
60	500	No Restrictions

Lane Widths


Max Lane Width	Optimum Lane Width	Minimum Lane Width	Absolute Minimum
(All Classes)	(All Classes)	(All Classes)	(Cars & Light Vehicles only)
4.0m	3.3m	3.0m	2.5m

Installation

- On arrival on site, park TTM vehicle safely and off the carriageway if possible.
- The TTOS identifies the works area and carries out a Dynamic Risk Assessment.
- Install the Roadworks Ahead signs, which are always the first signs to be installed.
- The safety zones and tapers shall now be measured out after which the position of the advance signs are calculated and TTM equipment laid out on the korb/ verge.
- The next signs to be installed are the Temporary Traffic Signals signs.
- Install advance central coning and Stop Here On Red sign.
- . Install the Roadworks End sign.
- Repeat the above sequence for all approaches to the works.
- 9. Place Keep Right arrow on kerb edge or verge at
- start of the lead in taper. 10. Set all signals to red.
 - Step out cones for lead in taper and install Keep Right arrow.
 - Install cones along safety zone and the length of the required works area.
- 13. Install exit taper.
- 14. TTMO carries out final check.
- 15. Inform workforce they may carry out the works.

Removal

- 1. Check all works personnel, plant, materials and debris are cleared and site is safe to traffic.
- Pull all TTM equipment around the works area to the kerb/verge under the protection of the longitudinal cone run and lead in taper.
- 3. Pull off the exit taper and longitudinal cone run back to the lead in taper.
- 4. Pull off the lead in taper and open carriageway to traffic.
- 5. Load TTM equipment onto the TTM vehicle.
- 6. Remove and load Advance Warning Signs.
- The last signs to be removed are the Roadworks Ahead signs.
- Check all equipment is loaded securely and safely on TTM vehicle.
- 9. Make a final check of the site ensuring all items are removed.
- Do not leave signs in place when no works are being carried out.
- 11. Leave site.



TEMPORARY TRAFFIC MANAGEMENT DESIGN

WORKS CLASSIFICATIONS (NEW)

Туре	Type of Road	Traffic Flow	Visibility	Duration
Static Type A	Works requiring full-time TTM	All	All	All
Static Type B	Works normally involving the use of 1-2 vehicles		All	≤ 12 hours
Static Type C	Works at discrete locations, and not presenting a traffic hazard		All	≤ 15 minutes
Semi-Static	Roadworks where operations are mobile or only stationary for very short periods, but where static signs and temporary traffic measures are used	Within traffic flow capacity	Good	≤ 15 minutes stop
Mobile	Roadworks where operations are mobile or only stationary for very short periods where mobile warning signs and temporary traffic measures are used		Good	≤ 15 minutes stop

TRAFFIC FLOW


Traffic flow is the volume of traffic that a given carriageway can accommodate when it is unrestricted by either traffic volume or weather conditions

Road Type	Road Width	Veh/ 3 min (busiest direction)
	< 6.0m	20 - 30
Single Carriageway, ≤ 60 km/h	≥ 6.0m and < 7.3m	40 - 50
	≥ 7.3m	60- 70
	< 6.0m	35 - 45
Single Carriageway, > 60 km/h	≥ 6.0m and < 7.3m	55 - 65
	≥ 7.3m	75 - 85
Dual Carriageway		60 - 65 per lane left open

ROAD CLASSIFICATIONS (NEW)


Road Classific	ation	Carriageway Type	Speed Limit
	i		≤ 30 km/h
	ii	Cingle	40 km/h
Level 1	iii	Single	50 km/h
			60 km/h
	iv —	Multi-Lane/Dual	≤ 60 km/h
	i	Single	80 km/h
Level 2	ii	Single	100 km/h
	i	Dual	80 km/h
Level 3	ii	Dual	≥ 100 km/h

PLATEMPORARY TRAFFIC MANAGEMENT DESIGN






TRAFFIC MANAGEMENT OPFRATIONS



TRAFFIC MANAGEMENT OPERATIONS

URBAN ROADS




TRAFFIC MANAGEMENT OPERATIONS

RURAL ROADS

CHAPTER 8

SEMI-STATIC OPERATIONS

Existing




New

Speed Visibilit	Vicihility	Hard Shoulder Works	Give/ Take		Stop/Go		
	VISIONICY	veh/ 3 min	veh/ 3 min	Works visibility	veh/ 3 min	Advance stop	Stop visibility
80 km/h	90m	120	20	160m	50	45m	90m
100 km/h	120m	130	20	215m	50	60m	120m

TRAFFIC MANAGEMENT OPERATIONS

GUIDANCE


MINOR ROADS



Speed	Ven/ To Works		Visibility to	Insufficier to ope		
	3min VISIDII	VISIDIIILY	vehicle	operatives	Advance stop	Stop visibility
60 km/h	15	60	60	00	15	60
80 km/h	15	60	60	90	45	90

TYPE C ROADWORKS

- Step 1: Vehicle
 - Legally parked/ Parked off the live lane
 - Good visibility (guidance given)
- Step 2: Roadworker
 - ≤ 60km/h
 - Not working in carriageway, or
 - Protected by fend (as per Step 1)
 - - Not working < 1.5m from carriageway, or
 - Working on a footway, or
 - Protected by fend (as per Step 1)



GUIDANCE

SHORT DURATION WORKS (TYPE C)





PEDESTRIANS AND VULNERABLE ROAD USFRS

PEDESTRIANS AND VULNERABLE ROAD USERS

D	IVERTING PEDE	STRIATION OF A	
	Spood	Visibili	ty (m)
	Speed	Pedestrian to traffic	Driver to crossing
	60 km/h	60m/lane	60
	50 km/h	45m/lane	45
	30 km/h	30m/lane	25

SHARED RUNNING LANE

Lane Width (m)

E T	

< 3.3	Should be supplemented with cyclist present sign. If existing lane width < 3.3m wide can be omitted. Signage only required if lane width is reduced
3.3 to 3.5	Can be used
3.5 to 4.0	To be avoided
> 4.0	Can be used



Standards/Operating Procedures/Training/Tools

www.tobarsegais.com

charlie@tobarsegais.com

087 2857237



Inform/ Promote/ Provide

www.instituteofasphalt.org





www.trafficsigns.ie